

DuraShield 12,000 FR Installation Specifications for Temporary Building Enclosures

Provide, install, maintain and intermittently remove and replace as required, a temporary

THOR Tarp DuraShield 12,000 FR building enclosure system

completely enclosing the perimeter of the Building from the Ground Floor to the Roof.

This system is to be installed on the outside of the pour stop to allow for the

composite concrete deck pours, fireproofing and topping activities. This system cannot be

attached to the perimeter fall protection system. The Sole use of the Durashield 12,000 FR Custom

Proprietary Enclosure Tarp is to be used. The tarps must be properly sized for each floor with

vertical 2" wide full height lacing lug pleats and match spaced brass grommets/eyelets @ 12" centers throughout so they can be attached to vertical cables spaced every 6 to 8 feet.

The strength of this system is in the horizontal and vertical stranded steel cables. The enclosure system includes, but is not limited to all tarps, cables, hardware, turnbuckles, supports and anchors.

The Structural Steel Contractor will be welding nuts on the pour stops starting 1'-0" in from the ends of the beams, 1" up and 1" down on the pour stops, 4'-0" on center. This will allow the

tarps to be attached to the horizontal cables running through the nuts, top and bottom of the pour stop, and allow the Curtain Wall Contractor and Exterior Framing Contractor to weld their

clips to the pour stop without compromising the enclosure system. All other support required for the system will be by this General Trades General Conditions Contractor. The system must

also incorporate all temporary doors, enclosures and all other temporary requirements as shown in Temporary Enclosure & Openings drawings. The entrances must be

soundly constructed out of wood and have all associated hardware and heavy-duty closers. This

contractor will be responsible for providing, maintaining, and removal of all temporary

measures. When the tarps are taken down, they must be folded up and turned over to owner.